

BID TABULATION

CITY OF ALLENTOWN
PURCHASING OFFICE

Marino Corporation
Attn: Richard Marino
1400 Cressman Road
P.O. Box 1209
Skippack, PA 19474
Phone: 610-584-1800
Fax: 610-584-8244
Email: ricmarino@marinocorp.com
10% Bid Bond

ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
1	Mobilization	1	LS	\$ 132,800.00	\$ 132,800.00
2	Traffic Control	1	LS	\$ 81,000.00	\$ 81,000.00
3	Remove concrete sidewalk for ADA ramp construction, any sawcutting is incidental to removal cost. Limits of sawcutting as directed by the Engineer. Remove and replace signs.	280	SY	\$ 46.00	\$ 12,880.00
4	Remove concrete curb, radius and straight. Sawcut curbing and in street surface to remove existing curb is incidental to curbing removal cost. Limits of sawcutting as directed by the Engineer.	350	LF	\$ 22.00	\$ 7,700.00
5	New concrete walk @ ramp locations, (4" concrete, 4" 2A compacted stone) - excludes DWS truncated dome areas	250	SY	\$ 149.00	\$ 37,250.00
6	New concrete walk @ DWS truncated dome pads (6" concrete, 4" 2A compacted stone) includes truncated domes + 3" allowance on all sides of domes.	260	SF	\$ 45.00	\$ 11,700.00
7	New concrete straight curb, 21", street restoration incidental to curb price, provide 2A compacted stone to surface. City Streets Department to pave.	110	LF	\$ 93.00	\$ 10,230.00
8	New concrete radius curb, 21", street restoration incidental to curb price, provide 2A compacted stone to surface. City Streets Department to pave.	240	LF	\$ 86.00	\$ 20,640.00
9	Construct new pedestrian light foundations per detail at plan locations.	35	EA	\$ 1,790.00	\$ 62,650.00
10	Install City pre-purchased pedestrian lights, City to supply poles and luminaires, pickup by Contractor at 641 S. 10th Street. All electrical wiring connections costs and outlet wiring are incidental to pole installations.	35	EA	\$ 1,800.00	\$ 63,000.00
11	Sawcut, excavate, install 2" schedule 40 PVC electrical conduit, concrete encase, install electrical wire, paving, joint seal using Crafcro rubberized sealant per plan detail.	2300	LF	\$ 108.00	\$ 248,400.00

BID TABULATION

CITY OF ALLENTOWN
PURCHASING OFFICE

Marino Corporation
Attn: Richard Marino
1400 Cressman Road
P.O. Box 1209
Skippack, PA 19474
Phone: 610-584-1800
Fax: 610-584-8244
Email: ricmarino@marinocorp.com
10% Bid Bond

ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
12	Junction Box supply and install	5	EA	\$ 1,600.00	\$ 8,000.00
13	Electrical Service from PPL Poles to Junction Boxes (include all costs including PPL costs and service extension to NE corner of Law and Chew Streets)	4	EA	\$ 6,340.00	\$ 25,360.00
14	Remove existing trees and root balls.	23	EA	\$ 1,470.00	\$ 33,810.00
15	Allowance for sidewalk removal and replacement 4" concrete walk on 4" 2A stone replacement related to rootball removals. Care to be taken in rootball removal, item approved by the Engineer in in the field on case by case basis. Remove and replace signs.	90	SY	\$ 212.00	\$ 19,080.00
16	Sawcut and remove sidewalk at 20 new tree pit locations. Pits to be 4' x 6' minimum if Bid Alt. #1 with grates is selected. Otherwise, 25 sf +- equivalent pit will be achieved from removal of existing adjacent slabs as directed by the Engineer.	20	EA	\$ 330.00	\$ 6,600.00
17	Trees "Okame Cherry" 3"-3 1/2" caliper Balled and Burlap, install within enlarged existing or new tree pit as located on the plans. Excavate and replace with new soil soil as per the contract specifications at the locations indicated on plans. Install commercial root barrier all sides of pit as specified.	32	EA	\$ 1,660.00	\$ 53,120.00
18	Remove existing and install replacement thermoplastic crosswalks (6" wide white stripes only) after Street Department paving at N. 6th Street and Chew Street per the plans.	1	L.S.	\$ 824.00	\$ 824.00
19	Remove existing and install 24" wide replacement thermoplastic stop bars after Street Department paving as indicated on the plans.	5	EA	\$ 361.00	\$ 1,805.00

BID TABULATION

CITY OF ALLENTOWN
PURCHASING OFFICE

Marino Corporation
Attn: Richard Marino
1400 Cressman Road
P.O. Box 1209
Skippack, PA 19474
Phone: 610-584-1800
Fax: 610-584-8244
Email: ricmarino@marinocorp.com
10% Bid Bond

ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
TOTAL BASE BID					
BID NO. 2016-30 HEART OF THE CITY IMPROVEMENTS					
CHEW STEET FROM 5TH TO 7TH STREETS					\$ 836,849.00
ALTERNATE NO. 1 (TREE GRATES AND SIDEWALK MODIFICATION/INSTALLATION)					
ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
20	Remove concrete walk to allow for new walk and tree grate ledge construction, any sawcutting is incidental to removal cost. (4th to 7th Streets)	80	SY	\$ 46.00	\$ 3,680.00
21	Replace concrete walk (plain, 6" thick concrete, 4" 2A compacted stone) Cast new ledge for tree grates into the new concrete (1 foot wide). (4th to 7th Streets).	80	SY	\$ 185.00	\$ 14,800.00
22	Remove existing trees and root balls between 4th and 5th streets.	4	EA	\$ 375.00	\$ 1,500.00
23	Trees "Okame Cherry" 3"-3 1/2" caliper Balled and Burlap, install within enlarged existing or new tree pit as located on the plans. Excavate and replace with new soil soil as per the contract specifications at the locations indicated on plans. Install commercial root barrier all sides of pit as specified.(Between 4th and 5th Streets).	4	EA	\$ 1,660.00	\$ 6,640.00
24	Tree Grates/Frames (4'x6' Neenah R8811 Black powder coated). Support on new cast sidewalk ledges. (Item quantities Include 5 tree locations between 4th and 5th Streets on Chew Street. These 5 locations must remove the existing tree. (4th to 7th Streets).	36	EA	\$ 1,300.00	\$ 46,800.00
25	Install new "Piano Key / Continental Crosswalk" thermoplastic crosswalks at N. 6th Street and Chew Street per the plans.	1	L.S.	\$ 1,975.00	\$ 1,975.00

BID TABULATION

CITY OF ALLENTOWN
PURCHASING OFFICE

Marino Corporation
Attn: Richard Marino
1400 Cressman Road
P.O. Box 1209
Skippack, PA 19474
Phone: 610-584-1800
Fax: 610-584-8244
Email: ricmarino@marinocorp.com
10% Bid Bond

ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
TOTAL ALTERNATE NO. 1 BID NO. 2016-30 HEART OF THE CITY IMPROVEMENTS CHEW STEET FROM 5TH TO 7TH STREETS					\$ 75,395.00
ALTERNATE NO. 2 (6TH STREET COLORED CROSSWALKS - SIMILAR TO 5TH STREET)					
ITEM NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
26	Decorative Crosswalks including Traffic Control, Existing Striping Eradication, Milling 2", New 2" Superpave, Curing, Installation Of Two-Part Polymer per Colors and to the Dimensions Matching the 5th Street Crosswalk Installation.	1500	SF	\$ 61.25	\$ 91,875.00
TOTAL ALTERNATE NO. 2 BID NO. 2016-30 HEART OF THE CITY IMPROVEMENTS CHEW STEET FROM 5TH TO 7TH STREETS					\$ 91,875.00