

Russo Concrete, LLC
Attn: Scott Russo, Owner
2461 Honeysuckle Road
Bethlehem, PA 18015
Phone: 484-239-9564
Email: scottrusso616@yahoo.com

10% Bid Bond

NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
1	STANDARD CONCRETE STRAIGHT CURB TYPE "B" (CITY) STEEL FORMS - NEW	5,900	L.F.	\$ 43.00	\$ 253,700.00
2	STANDARD CONCRETE RADIUS CURB TYPE "B" (CITY) STEEL - NEW	150	L.F.	\$ 43.00	\$ 6,450.00
3	REMOVAL OF CONCRETE CURB, STONE CURB AND/OR CURB & GUTTER STRAIGHT & RADIUS	6,000	L.F.	\$ 3.00	\$ 18,000.00
4	ADA HANDICAP DETECTABLE WARNING INSERTS PER DETAIL. D-14F, 14G, 14H (PAY LIMIT: DETECTABLE WARNING AREA + 3" EDGE ALLOWANCE) 6" AA CONCRETE / 2" STONE BED)	500	S.F.	\$ 50.00	\$ 25,000.00
5	CONCRETE SIDEWALK- TYPE "6" (6" AA CONCRETE / 2" STONE BED) INCLUDES STANDARD SIDEWALK & ADA RAMPS - NEW, 4" TOPSOIL, SEED, MULCH COMPLETE INCIDENTAL	100	S.F.	\$ 9.00	\$ 900.00
6	CONCRETE SIDEWALK- TYPE "5" (5" AA CONCRETE / 3" STONE BED) NEW, 4" TOPSOIL, SEED, MULCH COMPLETE INCIDENTAL	100	S.F.	\$ 8.75	\$ 875.00
7	CONCRETE SIDEWALK- TYPE "4" (4" AA CONCRETE / 4" STONE BED) NEW, 4" TOPSOIL, SEED, MULCH COMPLETE INCIDENTAL	26,400	S.F.	\$ 8.50	\$ 224,400.00
8	REMOVAL OF CONCRETE, STONE, OR SLATE BITUMINOUS MATERIAL IN SIDEWALK AND/OR PLANTER STRIP AREA	25,000	S.F.	\$ 1.50	\$ 37,500.00
9	REMOVAL OF BITUMINOUS DRIVEWAY APRONS	2,800	S.F.	\$ 1.50	\$ 4,200.00
10	PLACEMENT OF BITUMINOUS DRIVEWAY APRONS	700	S.F.	\$ 7.50	\$ 5,250.00
11	REMOVAL OF 6" CONCRETE DRIVEWAY APRONS	800	S.F.	\$ 2.00	\$ 1,600.00

Russo Concrete, LLC
Attn: Scott Russo, Owner
2461 Honeysuckle Road
Bethlehem, PA 18015
Phone: 484-239-9564
Email: scottrusso616@yahoo.com

10% Bid Bond

NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
12	PLACEMENT OF 6" DRIVEWAY APRONS	1,100	S.F.	\$ 8.75	\$ 9,625.00
13	REMOVAL OF 8" CONCRETE DRIVEWAY APRONS	1,500	S.F.	\$ 2.50	\$ 3,750.00
14	PLACEMENT OF 8" CONCRETE DRIVEWAY APRONS	2,100	S.F.	\$ 9.25	\$ 19,425.00
15	PLACEMENT OF CONCRETE IN PLANTER STRIP (TYPE 4) INCLUDES FILLING VOID AREA WITH 6" OF COMPACT (TO PREVENT TRIP HAZARD) TOPSOIL FOR FUTURE TREE PLACEMENT	2,800	S.F.	\$ 9.00	\$ 25,200.00
16	REMOVAL OF CONCRETE IN PLANTER STRIP	2,800	S.F.	\$ 2.50	\$ 7,000.00
17	PLACEMENT OF BITUMINOUS MATERIAL IN PLANTER STRIP (4" ID- 2 / 4" BED)	10	S.F.	\$ 10.00	\$ 100.00
18	EXTRA EXCAVATION	5	C.Y.	\$ 50.00	\$ 250.00
19	ROCK EXCAVATION (MINIMUM 1.0 / C.Y.)	1	C.Y.	\$ 300.00	\$ 300.00
20	STANDARD TREE PLATE (3/8" THICKNESS)	5	L.F.	\$ 75.00	\$ 375.00
21	STEEL DIAMOND PLATE COVERED DRAINAGE CHANNEL	10	L.F.	\$ 100.00	\$ 1,000.00
22	3" DIAMETER DUCTILE DRAINAGE PIPE	10	L.F.	\$ 5.00	\$ 50.00

Russo Concrete, LLC
Attn: Scott Russo, Owner
2461 Honeysuckle Road
Bethlehem, PA 18015
Phone: 484-239-9564
Email: scottrusso616@yahoo.com

10% Bid Bond

NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
23	SAWCUTTING CONCRETE WALK AND/OR BITUMINOUS SIDEWALK AS DIRECTED BY THE ENGINEER. ALL OTHER SAWCUTTING IS INCIDENTAL TO THE RELATED UNIT PRICE ITEM. (IE: CURBING, ETC.)	500	L.F.	\$ 5.00	\$ 2,500.00
24	PLACEMENT OF BRICK SIDEWALK COMPLETE	100	S.F.	\$ 25.00	\$ 2,500.00
25	PLACEMENT OF BRICK CROSSOVER	100	S.F.	\$ 30.00	\$ 3,000.00
26	GEOTEXTILES FOR STABILIZATION (4 OZ.)	20	S.Y.	\$ 10.00	\$ 200.00
27	TREE REMOVAL 8" TO 18" (DBH)*	1	EA	\$ 2,000.00	\$ 2,000.00
28	TREE REMOVAL 19" TO 36" (DBH)	1	EA	\$ 2,750.00	\$ 2,750.00
29	TREE REMOVAL OVER 36 (DBH)	1	EA	\$ 3,500.00	\$ 3,500.00
30	TREE STUMP REMOVAL ALL SIZES	1	EA	\$ 750.00	\$ 750.00
31	DRIVEWAY REPLACEMENT 2" ID-2	5	S.Y.	\$ 30.00	\$ 150.00
32	TRIP STOP JOINT INSTALLED AS DIRECTED - 5" DEPTH IN 5" SIDEWALK, TS-5 TRIPSTOP MATERIAL	400	L.F.	\$ 16.00	\$ 6,400.00
33	WALL PARGING / STUCCO AT WALK GRADE CHANGE	20	S.F.	\$ 25.00	\$ 500.00

Bid No. 2016-05
 Curb Sidewalk for the 2016 Streets Program

BID TABULATION
 CITY OF ALLENTOWN
 PURCHASING OFFICE

Bid Opening: March 23, 2016
 At 2:00 p.m.

Russo Concrete, LLC
 Attn: Scott Russo, Owner
 2461 Honeysuckle Road
 Bethlehem, PA 18015
 Phone: 484-239-9564
 Email: scottrusso616@yahoo.com

10% Bid Bond

NO.	PRODUCTS/SERVICES	QTY	UNIT	UNIT PRICE	EXTENSION
34	4" WIDE CURB CHEEK WALL INSTALLED AS DIRECTED PER DETAIL TO 6" BELOW SIDEWALK SURFACE	20	L.F.	\$ 30.00	\$ 600.00
35	MANHOLE ADJUSTMENT FOR GRADE CHANGE	1	L.S.	\$ 300.00	\$ 300.00
36	STREET RESTORATION - 1 1/2" ID-2 WEARING COURSE 5" BCBC, AND SEALING GUTTER FOR HANDICAP RAMP PAVING FILETS ONLY, ALL OTHER STREET RESTORATION IS INCIDENTAL TO CURB UNIT PRICE	10	S.Y.	\$ 85.00	\$ 850.00
TOTAL BID NO. 2016-05 CURB & SIDEWALK STREETS 2016 STREETS PROGRAM- VARIOUS LOCATIONS					\$ 670,950.00